



**COMPETITIVE & LIVABLE CITY OF KARACHI
INVESTMENT DEPARTMENT
GOVERNMENT OF SINDH**



REQUEST FOR QUOTATION
(RFQ)

RENOVATION, CONSTRUCTION AND UPGRADATION OF CLICK OFFICE

REF: No. PK-SID-537683-CW-RFQ

ISSUE DATE: 25.02.2026



**COMPETITIVE & LIVABLE CITY OF KARACHI
INVESTMENT DEPARTMENT
GOVERNMENT OF SINDH**



M/S _____

1. The Government of Sindh (the Client) has received financing from World Bank (the Bank) in the form of a credit towards the cost of the Competitive and Livable City of Karachi (CLICK) Project. The Project Director, Project Implementation Unit, CLICK, Karachi, the implementing agency of the Client, intends to apply a portion of the proceeds of this credit to eligible payments under the Purchase Order / Contract for which this RFQ is issued.
2. The Project Director, Project Implementation Unit – CLICK, now invites quotations from firm registered with the relevant tax authorities, for supply of IT Equipment.
3. The deliverables must be completed within 04 weeks from the date of Purchase order.
4. Quoted rates must be inclusive of all applicable taxes and levies. However, in case SST / GST is applicable, it should be clearly mentioned separately in the quotation and on the Price Schedule enclosed as Annex-A.
5. The received quotations will be evaluated as per the 'RFQ' method of procurement in accordance with the World Bank Procurement Regulations for IPF Borrowers 2020, available on the World Bank website.
6. The quotation, along with complete details of the bidder's profile, relevant experience, and supporting documents, may be addressed and submitted to the office of the Project Director (PIU) – CLICK at the address given below, on or before 09th March 2026 by 12.00 hours.
7. The quotation must remain valid for at least thirty (30) days from the date of submission.

8. The work done against the requirement shall be subject to inspection, verification and approval of Senior Automation Specialist–CLICK.
9. All payments will be made through crossed cheque within thirty (30) days of receipt of the vendor's invoice, duly supported with job completion Certificate duly verified by the Senior Automation Specialist–CLICK.
10. Retention / Performance Security: @ 7.5% of the invoiced amount shall be retained as performance security till 29th May 2026. The retained amount will be released upon satisfactory performance duly verified by Senior Automation Specialist-CLICK.

Project Director (CLICK)
Sindh Investment Department
Government of Sindh
Address: First Floor, Block B,
FTC Building, Shakra-e-Faisal,
Karachi
Telephone: +92-21-99207512-14

PRICE SCHEDULE

Annex-A.

ITEM No.	Description	Unit	Qty	Unit Rate (PKR)	Amount (PKR)
1	<p>DISMANTLING, REMOVAL & DISPOSAL OF EXISTING INSTALLATIONS</p> <p>Dismantling and removal of existing complete civil works including civil structures, wooden partitions, glass partitions, doors, windows, furniture and fixtures, false ceilings, washroom fixtures and fittings, water supply and drainage systems, electrical works, IT and telephone cabling and fittings including switches, sockets, light fittings, conduits, trunking, panels and all associated accessories.</p> <p>The item includes careful disconnection, protection of adjacent structures, dismantling, loading, transportation, and safe disposal of all dismantled materials and debris at approved dumping sites, complete in all respects, to the satisfaction of the Engineer / Authority.</p>	Sqft	1800		
2	<p>WOODEN PARTITION WALLS</p> <p>Providing and fixing wooden partition wall Thickness 3" MDF (Lassani) Alnoor Brand 16mm on both sided Partal wooden framing size 2"x1"high about 8' with skirting height 4" wooden veneer Alnoor Brand Size: 4'x8' thickness 04mm, including best quality hardware, adhesive glue and fittings etc., complete in all respect as Shown on the drawings specifications and/or as directed by the Authority</p>	Sqft	5700		
3	<p>FIBER CEMENT BOARD PARTITION WALLS</p> <p>Providing and fixing of Fiber Cement Board wall partition for Wash Rooms & Kitchen</p>	Sqft	1000		

4	GLASS PARTITION Each Executive Staff Cabin/Office having Front Glass Partition 12mm with motorized floor hinges/ closer stoppers, locks as the existing design and look. Including high quality hardware complete in all respect as Shown on the drawings specifications and/or as directed by the Authority	Sqft	1900		
5	FALSE CELING Providing and Fixing False Ceiling Material: Gypsum compound board Sheet Size: 4'x8' thickness 12mm imported United/Elephant Brand Structure: The Furring U Channel is a crucial premium galvanized steel width 47mm Height 17mm imported and wooden veneer Rafter with Polish for only Committee Room	Sqft	4500		
6	PORCELAIN TILES ON FLOOR & SKIRTING Providing and laying glazed full body Porcelain as per existing design color pattern and size 24"x24" the Skirting size: height 4" and length as per Tiles, China or bone color Master full body porcelain or equivalent, setting in Stile dry Bond (with cement), with matching color imported Grout. Complete in all respect, including curing, cleaning, finishing & hacking/chipping of existing surface for bonding where necessary, etc. as per specifications and/or as directed by the Authority	Sqft	2800		
7	WOODEN FLOORING Providing and laying of wood flooring with insulator as per approved color for floor, for Committee Room & executive office area as per specifications and/or as directed by the Authority	Sqft	4500		
8	PAINT Provide and apply with roller high quality solvent-based <i>matt finish enamel</i> paint NIPPON minimum three coats of approved shade over a coat	Sqft	8500		

	of primer surfaces, base preparation, primer, smooth filling etc. complete in all respect as Shown on the drawings specifications and/or as directed by the Authority				
9	WOODED DOORS Provide and fixing of wooden doors Pertal Panel with complete Accessories	Sqft	100		
10	WALL PAPER & FOISTED VINYL FILM Provide and pasting of wall paper on wooden wall and foisted vinyl film on glass wall and doors as directed by the Authority	Sqft	3420		
11	MARBLE TOP Provide and Fixing in Kitchen counter top and Staff's Dinning counter top	Sqft	90		
12	<u>PLUMBING & SANITARY WORKS</u>				
	Provide and Fixing Drainage Pipes line, Water Supply Pipes Executive, Female, Staff's Washroom and Ablution Area	Rft	210		
	Provide and Fixing Water Supply Pipes Executive, Female, Staff's Washroom and Ablution Area	Rft	350		
	Providing, supplying, and fixing of Western Water Closet with seat cover, including Muslim shower (health faucet) and double bib cock , fittings, connections, brackets, flexible hoses, traps, testing, complete in all respects as per standard specification complete with all necessary	Nos.	02 Sets		
	Providing, supplying, and fixing of vanity wash basin complete with tee cocks / angle valves, basin mixer, waste pipe, bottle trap, flexible connections , brackets, accessories, and all necessary plumbing connections. For Executive and Female Washrooms	Nos.	02 Sets		
	Providing, supplying, and fixing of Western Water Closet with Flush Tank, including Muslim shower and double bib cock , complete with all	Nos.	02 Sets		

	necessary fittings, for Staff's washrooms as per standard specification				
	Providing, supplying, and fixing Floor Drains	Nos.	08		
	Providing, supplying, and fixing Executive wash room complete accessories sets	Nos.	01		
	Providing, supplying, and fixing Females & Staff wash room complete accessories sets	Nos.	02		
	Providing, supplying, and fixing Ablution Area	Nos.	04		
13	ELECTRICAL WORKS				
	<p>Main 3 phase Supply Line from Distribution Board (DB)</p> <ul style="list-style-type: none"> ○ KE (K-Electric) power ○ FMCL (Emergency/Generator supply) <p>Complete main supply shall be carried out using: 7/0.29 mm² cable (L + N + E)</p> <p>All wiring to be laid in 25 mm diameter PVC conduit pipe concealed in wall and ceiling</p>	Rft	1800		
	<p>Providing, wiring, termination, and connection of 240 power supply points for lights, switches, and multi sockets, comprising:</p> <ul style="list-style-type: none"> ○ 70% supply from KE (K-Electric) ○ 30% supply from FMCL (Generator / Backup source) <p>Including supply and installation of: Approved quality copper wiring 3/0.29 mm² cable (L + N + E) in PVC conduits. Switches, sockets, switch plates, and accessories. Proper segregation of KE and FMCL circuits.</p>	Rft	7200		
	Electrical switch	Nos.	40		
	Multi Socket	Nos.	80.		
	LED Ceiling Lights 12 W / 18 W	Nos.	130		
14	NETWORKING				
	<p>Structured Cabling System</p> <p>3M VOL-PPCB-F48K Port RJ45 Patch Panel Cat6 STP Feed Through,</p>	Nos.	40		

	<p>Coupler Network Panel 19 Inch, Inline Keystone Ethernet Patch Panel with Back Bar</p> <p>Complete structured cabling using: CAT-6 UTP Cable</p> <p>Cabling to be laid in:</p> <ul style="list-style-type: none"> • 25 mm dia PVC conduit pipe concealed in walls/false ceiling. • All cables to be run from the Main Network Rack to each office/room in star topology. <p>LAN Points / Data Point Wall Socket RJ 45</p>				
	<p>TELEPHONE LINE SYSTEM</p> <ul style="list-style-type: none"> • Panasonic PABX Models hybrid PBX system supporting up to 8 lines and 24 extensions • Panasonic Console KX-DT54 • Complete Installation 				
	Total Value				
	Add GST (if Applicable)				
	Grand Total value				